





1. ALL WORK TO BE PERFORMED UNDER THIS CONTRACT WILL BE WITHIN THE PUBLIC RIGHT-OF-WAY (ROW), INCLUDING PERMANENT EASEMENTS AND TEMPORARY EASEMENTS SPECIFIC TO THIS PROJECT. THE CONTRACTOR IS TO ASSURE HIMSELF THAT ALL WORK IS BEING PERFORMED WITHIN THE ROW, INCLUDING BUT NOT LIMITED TO VEHICLE ACCESS; STORAGE OF EQUIPMENT, MATERIALS, DEBRIS AND WASTE; LANDSCAPING; VEGETATION REMOVAL AND MANAGEMENT; GRADING, SEEDING AND THE INSTALLATION OF TURF; AND THE INSTALLATION OF ANY FENCES OR PROTECTIVE BARRIER. IF THE CONTRACTOR IS UNABLE TO IDENTIFY THE LIMITS OF THE RIGHTS-OF-WAY WHEN THE CONTRACT CALLS FOR WORK IN THOSE VICINITIES, THE CONTRACTOR MUST CONTACT THE CITY FOR DEFINITIVE BOUNDARY DETERMINATIONS BEFORE ANY WORK MAY BE INITIATED AT THOSE LOCATIONS. RELEASES FOR ANY NON-ESSENTIAL CONTRACT WORK OUTSIDE OF THE EXISTING RIGHTS-OF-WAY, INCLUDING PLANTINGS, LANDSCAPING OR DRIVEWAY ENHANCEMENT, WILL BE PROVIDED BY THE CITY AND IN NO INSTANCES ARE TO BE SECURED BY THE CONTRACTOR. THE CONTRACTOR SHALL NOT INVADE UPON PRIVATE PROPERTIES, LANDS OR BUILDINGS OUTSIDE THE RIGHTS-OF-WAY FOR ANY REASON WITHOUT FIRST SECURING WRITTEN PERMISSION FROM THE PROPERTY OWNER. THE CONTRACTOR WILL BE HELD LIABLE FOR ANY DAMAGES DONE. ANY SUCH INJURIES OR DAMAGES SHALL BE SATISFACTORILY REPAIRED OR ITEMS REPLACED AT THE CONTRACTOR'S EXPENSE.

2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING ALL ELEVATIONS AND DIMENSIONS TO ENSURE THAT WHERE EXISTING CURB RAMPS ARE BEING REPLACED, THE FINAL LAYOUT OF CURB RAMPS, TURNING SPACES, CLEAR SPACES, SIDE FLARES, DETECTABLE WARNING UNITS, AND CURB INSTALLATIONS MEET ADA REQUIREMENTS PRIOR TO POURING CONCRETE AND PLACING ASPHALT OR PAVERS. THE SURVEY WORK NECESSARY TO MEET THESE REQUIREMENTS SHALL BE INCLUDED IN THE COST OF ITEM 625.01 - SURVEY OPERATIONS.
3. IN THIS MILLING AND OVERLAY PROJECT, THE PROPOSED ROADWAY SHALL BE INSTALLED AS PER THE TYPICAL SECTION, MEETING GRADES AND CROSS SLOPES. THERE MAY BE AREAS ALONG THE CURB IN WHICH PROPOSED ROADWAY ELEVATIONS MAY DIFFER SLIGHTLY FROM THE EXISTING. SHOULD ADJUSTMENT OF GAS VALVES BE REQUIRED, CONTRACTOR SHALL NOTIFY CENTRAL HUDSON GAS AND ELECTRIC (CHG&E), WHO WILL PREFORM THE WORK. CHG&E WILL REQUIRE 6 WEEKS TO PREFORM THIS WORK UPON NOTIFICATION. ADJUSTMENTS TO WATER VALVES IF REQUIRED, SHALL BE PERFORMED BY THE CONTRACTOR AND PAID UNDER ITEM 663.33. A QUANTITY OF 99 IS ASSUMED FOR THIS PROJECT. DUE TO THEIR CONDITION, ALL SEWER MANHOLES WITHIN THE PROPOSED CONSTRUCTION THAT ARE NOT BEING REPLACED SHALL BE ALTERED, ITEM 662.62000010. DRAINAGE STRUCTURES SHALL BE ALTERED, ADJUSTED, OR REPLACED AS PER THE DRAINAGE AND UTILITY PLANS (OUP SERIES OF DRAWINGS).



			CITY OF BEACON		
DATE: OCTOBER 2023			PROJECT: PIN 8757.80 & PIN 8757.30 REHABILITATION OF TELLER & FISHKILL AVENUES		NO: GNP-01
PE DB	DE SM	PM DW	GENERAL PLANS		SCALE: AS SHOWN
					SHEET 17 OF 64